

VILLAGE OF WILMETTE

Notice of Award of Contract

For constructing an ornamental street lighting system in Ridge Road from Lake Avenue to a point three hundred and ninety (390) feet north of the north line of Lake Avenue and in other streets.

(Wilmette Special Assessment No. 195.)
Wilmette, Illinois, August 3rd, 1927.

Notice is hereby given to all persons interested that the bids for the construction of an ornamental electric lighting system along the west side of Ridge Road from Lake Avenue to a point three hundred and ninety (390) feet north of the north line of Lake Avenue and along other streets in the Village of Wilmette, Cook County, Illinois in accordance with the ordinance (Wilmette Special Assessment No. 195) were opened on the 2nd day of August, 1927 and A. M. Ryckoff being the lowest responsible bidder, the contract was awarded to said A. M. Ryckoff on the 2nd day of August, 1927. Said bid is for the work as a whole and is as follows:

- 187 Ornamental Concrete Street Lighting Standards and Fixtures, inclusive of all labor and material for erection in post hole, complete at \$104.00 each \$19,448.00
- 18 Of the above One Hundred Eighty Seven (187) Concrete Standards to be equipped with a four (4) inch by four and one-half (4½) inch Red Prismatic Mirror Reflector located two (2) feet six (6) inches above the base of the ornamental section and forming an integral part of the Standard, at \$20.00 each \$3,660.00
- 187 Post Holes thirty (30) inches in diameter and four (4) feet deep, in-

cluding all of the necessary labor, at \$4.80 each \$897.60

144 100 Candle-power Mazda "C" 6.6 Ampere lamps, designed for tip-up burning, installed at \$2.66 each \$383.04

55 250 Candle-power Mazda "C" 6.6 Ampere lamps designed for tip-up burning, installed at \$3.60 each \$198.00

12,600 Lineal Feet of trenching six (6) inches wide and twenty-four (24) inches deep including excavation, backfilling and restoration of parkways, at \$0.09 per lineal foot \$3,834.00

2,235 Lineal Feet genuine wrought iron pipe two and one-half (2½) inches internal diameter installed under streets, alleys, side-walks and driveway crossings, at \$1.50 per lineal foot \$3,352.50

400 Lineal Feet genuine wrought iron pipe three (3) inches internal diameter installed under streets, alleys, side-walks and driveway crossings at \$2.10 per lineal foot \$840.00

8,700 Feet No. 8 Brown and Sharpe gauge solid single conductor 1500-Volt cable laid complete in parkways and in pipe including all labor at \$0.16½ per foot \$12,985.50

10,600 Feet No. 8 Brown and Sharpe gauge solid copper single conductor 5000-Volt cable laid complete in parkways and in pipe conduits properly connected to transformers and pole heads, including all labor, at \$0.28 per foot \$2,968.00

4 Five (5) KVA Oil Cooled Transformers Sixty (60) Cycle, Six and six-tenths (6.6) Ampere Primary, six and six-tenths (6.6) Ampere Secondary, complete inclusive of all labor and material for installing in manhole and connecting primary and secondary leads with disconnecting devices, at \$220.00 each \$880.00

2 Three (3) KVA Oil Cooled Transformers Sixty (60) Cycle Six and six-tenths (6.6) Ampere primary, Six and six-tenths (6.6) secondary, complete inclusive of all labor and material for installing in manhole and connecting primary and secondary leads with disconnecting devices, at \$195.00 each \$585.00

2 Concrete Manholes each six (6) feet long by six (6) feet wide inside dimensions and six (6) feet from bottom of top slab to inside bottom of manhole. Walls and floor to be eight (8) inches thick. Each manhole to be furnished with an eight (8) inch thick concrete roof slab reinforced with three-quarters (¾) inch square reinforcing rods placed six (6) inches center to center and not less than one (1) inch from bottom of slab; the top surface of slab to be finished smooth and with an opening in the center of the slab to contain a cast iron frame with cast iron cover weighing not less than seven hundred (700) pounds, the cover to be twenty-eight (28) inches by thirty-two (32) inches and set to established grade. The floor of said manhole to be eight (8) feet four (4) inches square and slope towards a drain to be installed in the wall at one end of the manhole and at the surface of the floor, said drain to be equipped with a four (4) inch back pressure valve and connected to sewer otherwise provided for. All concrete to be composed by volume of three (3) parts of clean torpede sand, five (5) parts of washed gravel or crushed stone of the size to pass through a three-quarters (¾) inch screen and be retained on a one-half (½) inch screen, and one (1) part of Portland Cement, the whole to be mixed with clean water

free from acid, alkali or other deleterious matter. Including excavating, backfill, cable entrances, all transformer supports and ground cone, at \$350.00 each \$700.00

12 Existing lighting standards to be wired and connected to the herein proposed street lighting system at \$16.00 each \$192.00

28 Street signs with brackets to be furnished and installed at \$20.00 each \$560.00

Total \$47,988.64

The owners of a majority of the frontage of the lots and lands upon said streets wherein the said work is to be done may within ten (10) days of the date hereof as provided by law elect to take said work and enter into a written contract to do said work at ten per centum (10%) less than the price at which the same has been awarded.

EARL E. ORNER
JOHN CLARK BAKER
ERNEST C. CAZEL
CLARENCE E. DRAYER
PAUL A. HOFFMAN
HANS VON REINSBERG
JOHN F. WIEDLIN

Board of Local Improvements of the Village of Wilmette 145-116

Mr. and Mrs. B. N. Cox and their two children of 116 Elmwood avenue returned Sunday from a stay at Merimac, Wis. During their absence, Mrs. Cox's brother and sister-in-law, Mr. and Mrs. Lawrence Roberts of Evanston, occupied the house.



EARLY FALL APPAREL

Presenting the newest and smartest fashions for Misses and Women. Early selections always fulfill the desire to be different from the ordinary

Continuing Final Clearance
Summer Apparel

LEWIS
INCORPORATED
C.S. Breckenridge, Pres.

1606 Chicago Avenue at Davis Street
EVANSTON

