

BADMINTON CLUB ORGANIZED (cont'd) For further information, contact any member of the executive.

Remember: WEDNESDAY NIGHT IS BADMINTON NIGHT AT TERRACE BAY.

--0--

AT THE HYDRO PROJECT A major news item from the Hydro Project is the fact that to-day (Wednesday October 22nd) a cofferdam will be blown up which will re-route the flow of the Aguasabon River through a new diversion channel in such a manner as to permit easy accessibility to the former river bed thus enabling work to be proceeded with on the main dam.

The cofferdam which will be eliminated, has served as a barrier to the diversion channel which has been hewn in solid rock. Meanwhile a second cofferdam is under construction across the river, upstream from the main dam. This cofferdam will help to route the flow of water down the diversion channel.

In order to lower the general level of water in the river, the main control dam at the south end of Long Lake will be closed to-day. This will result in a considerable lessening of the volume of water flowing over the Aguasabon Falls.

--0--

FROM THE RECORDS

Two Years Ago at Terrace Bay

Final surveys were being made in this general area prior to the selection of the present location for the project. Terrace Bay was nothing more than a heavily wooded area. A flagstop on the C.P.R. main line called Black, Ontario was located near our present railroad station.

18 Months Ago at Terrace Bay

Diamond drill crews were engaged in probing soil conditions prior to selection of the actual Millsite.

Two camp buildings were complete and work was progressing satisfactorily on the erection of 5 prefabricated buildings to be used as bunkhouses, mess halls, and an office.

A stable was being erected also as horses were required to haul firewood and supplies from the railroad.

12 Months Ago at Terrace Bay

In the Townsite, 75 house foundations were complete; 31 houses had been erected and the finishing carpentry work was completed in one house while George Aarnio's carpenter crew worked on the interior finishing of 5 other houses simultaneously.

A water line was being installed down Highway 17 from the C P.R. tracks to the Townsite - and a temporary diesel power house was being finished.

At the Millsite

Steel had been erected for the Pulp Storage Building - concrete foundations were in for the recovery boiler and excavation work for the steam boiler was finished. Survey work had started on the Blackbird Creek drainage area.

In the Lower Camp

A boiler was being installed at the base of the water tower to prevent it from freezing---Additional bunkhouses were being constructed to take care of staff and crew expansion which for the first time exceeded the 400 mark.

--0--