shall be lowered westerly along the center line and said center line extended of Elder Lane to a point 421 feet easterly from the easterly line extended of Sheridan Road where the elevation of said sewer shall be 8.3 feet below datum; thence along said line to a manhole 380 feet east of the east line extended of Sheridan Road where the elevation of the said sewer shall be and now is 9.1 feet above datum; from and discharging into Lake Michigan at a point on the center line of Elder Lane extended 596 feet easterly from the easterly line extended of Sheridan Road at an elevation of 6.3 feet below datum, a cast iron pipe sewer of cylindrical shape having an internal diameter of 20 inches shall be constructed westerly along said center line and center line extended of Elder Lane to a point 421 feet easterly from the easterly line extended of Sheridan Road where the elevation of said sewer shall be 6.3 feet below datum; thence westerly to a manhole 380 feet easterly from the easterly line extended of Sheridan Road and 10 feet southerly from the center line of Elder Lane where the elevation of said sewer shall be 9.1 feet above datum; from and discharging into the last mentioned manhole at an elevation of 9.1 feet above datum, a tile pipe sewer having an internal diameter of 27 inches shall be constructed westerly in Elder Lane along a line 10 feet southerly from and parallel to the center line of Elder Lane to a manhole on the easterly line extended of Sheridan Road where the elevation of said sewer shall be 17.5 feet above datum; from the last mentioned manhole at an elevation of 17.5 feet above datum, a tile pipe sewer having an internal diameter of 27 inches shall be constructed northerly at an angle of 45° with the center line of Elder Lane to and discharging into the present 24-inch by 36-inch egg-shaped brick sewer on the center line of Elder Lane, at an elevation of 14.4 feet above datum; from and discharging into the last mentioned manhole at an elevation of 17.5 feet above datum, a brick sewer of cylindrical shape having an internal diameter of 51 inches and made with a double ring of sewer brick laid edgewise shall be constructed westerly to a manhole 22 feet easterly from the westerly line of Sheridan Road and 30 feet northerly from the southerly line extended of Elder Lane where the elevation of said sewer shall be 17.8 feet above datum; thence westerly to a manhole 30 feet north of the south line extended of Elder Lane from the west and 10 feet east of the center line extended of Essex Road where the elevation of said sewer shall be 18.3 feet above datum; from and discharging into the last mentioned manhole at an elevation of 18.6 feet above datum; a brick sewer of cylindrical shape having an internal diameter of 48 inches and made with a double ring of sewer brick laid edgewise shall be constructed west in Elder Lane along a line 30 feet north of the south line and said south line extended of Elder Lane, 335 feet to a manhole where the elevation of said sewer shall be 19.0 feet above datum; thence west along said line to a manhole 23 feet west of the east line extended of Woodland Avenue where the elevation of said sewer shall be 19.4 feet above datum; from and discharging into the last mentioned manhole at an elevation of 19.4 feet above datum, a brick sewer of cylindrical shape having an internal diameter of 42 inches made with a double ring of sewer brick laid edgewise shall be constructed west along said line 203 feet to a manhole where the elevation of said sewer shall be 20.6 feet above datum; thence west along said line to a manhole 23 feet west of the east line extended of Fairview Avenue where the elevation of said sewer shall be 21.6 feet above datum; thence southwesterly 180 feet to a manhole 23 feet north of the south line of Elder Lane where the elevation of said sewer shall be 22.4 feet above datum; thence west along a line 23 feet north of and parallel to the south line and said south line extended of Elder Lane to a manhole 23 feet west of the east line extended of Myrtle Street where the elevation of said sewer shall be 25.0 feet above datum; from and discharging into the last mentioned manhole at an elevation of 25.0 feet above datum; a brick sewer of cylindrical shape, having an internal diameter of 36 inches made with a double ring of sewer brick laid edgewise shall be constructed west along said line 220 feet to a manhole where the elevation of said sewer shall be 26.5 feet above datum; thence west along said line to a manhole 23 feet west of the east line extended of Poplar Street where the elevation of said sewer shall be 26.9 feet above datum; from and discharging into the last mentioned manhole at an elevation of 26.9 feet above datum, a brick sewer of cylindrical shape having an internal diameter of 33 inches, made with a double ring of sewer brick laid edgewise, shall be constructed west along said line to a manhole 35 feet westerly from the easterly line extended of Wilson Street measured at right angles thereto where the elevation of said sewer shall be 28.0 feet above datum; from and discharging into the last mentioned manhole at an elevation of 28.0 feet above datum, a brick sewer of cylindrical shape having an internal diameter of 33 inches made with a double ring of sewer brick laid edgewise shall be constructed northerly along a line 35 feet westerly from and parallel to the easterly line and said easterly line extended of Wilson Street to a manhole the north edge of which said manhole shall be 25 feet north of the north line extended of Elder Lane where the elevation of said sewer shall be 29.0 feet above datum; from and discharging into a manhole 30 feet northerly from the southerly line of Elder Lane and 22 feet easterly from the westerly line extended of Sheridan Road at an elevation of 18.0 feet above datum, a tile pipe sewer having an internal diameter of 24 inches shall be constructed southerly in Sheridan Road along a line 22 feet easterly from and parallel to the westerly line and said westerly line extended of Sheridan Road 322 feet to a manhole where the elevation of said sewer shall be 18.39 feet above datum; thence southerly along said line 322 feet to a manhole where the elevation of said sewer shall be 18.72 feet above datum; thence southerly 322 feet along said line to a manhole where the elevation of said sewer shall be 19.17 feet above datum; from and discharging into the last mentioned manhole at an elevation of 19.17 feet above datum a tile pipe sewer having an internal diameter of 18 inches shall be constructed southerly along said line 322 feet to a manhole where the elevation of said sewer shall be 19.81 feet above datum; thence southerly along said line 322 feet to a manhole where the elevation of said sewer shall be 20.45 feet above datum; from and discharging into the last mentioned manhole at an elevation of 20.45 feet above datum, a tile pipe sewer having an internal diameter of 15 inches shall be constructed southerly along said line to a manhole 15 feet southerly from the northerly line extended of Winnetka Avenue where the elevation of said sewer shall be 21.25 feet above datum; from and discharging into the last mentioned manhole at an elevation of 21.25 feet above datum, a tile pipe sewer having an internal diameter of 15 inches shall be constructed westerly in Winnetka Avenue along a line 15 feet southerly from and parallel to the northerly line and said northerly line extended of Winnetka Avenue to a manhole 15 feet south of the north line extended of Winnetka Avenue from the west where the elevation of said sewer shall be 22.14 feet above datum; from and discharging into a manhole 15 feet west of the east line of Essex Road extended from the north and 15 feet south of the north line extended of Winnetka Avenue, at an elevation of 20.35 feet above datum, a tile pipe sewer having an internal diameter of 15 inches shall be constructed east in Winnetka Avenue along a line 15 feet south of and parallel to the north line and said north line extended of Winnetka Avenue 295 feet to a manhole where the elevation of said sewer shall be 20.68 feet above datum; thence east along said line 295 feet to a manhole where the elevation of said sewer shall be 21.13 feet above datum; thence east along said line 295 feet to a manhole where the elevation of said sewer shall be 21.58 feet above datum; thence east along said line to a manhole 15 feet southerly from the northerly line of Winnetka Avenue extended from the east where the elevation of said sewer shall be 22.0 feet above datum; from and discharging into a manhole 15 feet west of the east line of Essex Road extended from the north and 15 feet south of the north line extended of Winnetka Avenue, at an elevation of 20.25 feet above datum, a brick sewer of cylindrical shape having an internal diameter of 30 inches made with a double ring of sewer brick laid edgewise, shall be constructed west in Winnetka Avenue along a line 15 feet south of and parallel to the north line and said north line extended of Winnetka Avenue to a manhole 15 feet east of the west line extended of Essex Road from the south where the elevation of said sewer shall be 20.33 feet above datum; thence west along said line to a manhole 238 feet west of the west line extended from the north of Essex Road where the elevation of said sewer shall be 20.63 feet above datum; thence west along said line 273 feet to a manhole where the elevation of said sewer shall be 21.0 feet above datum; from and discharging into the last mentioned manhole at an elevation of 21.0 feet above datum, a tile pipe sewer having an internal diameter of 22 inches shall be constructed west along said line to a manhole 15 feet west of the east line extended of Woodland Avenue where the elevation of said sewer shall be 21.63 feet above datum; thence west along said line 175 feet to a manhole where the elevation of said sewer shall be 22.01 feet above datum; from and discharging into the last mentioned manhole at an elevation of 22.8 feet above datum a tile pipe sewer having an internal diameter of 18 inches shall be constructed west along said line 180 feet to a manhole where the elevation of said sewer shall be 23.64 feet above datum; thence west along said line 240 feet to a manhole where the elevation of said sewer shall be 24.75 feet above datum; thence west along said line 175 feet to a manhole where the elevation of said sewer shall be 25.6 feet above datum; thence west along said line 254 feet to a manhole where the elevation of said sewer shall be 27.79 feet above datum; thence west along said line 254 feet to a manhole where the elevation of said sewer shall be 29.0 feet above datum; from and discharging into the last mentioned manhole at an elevation of 29.0 feet above datum, a tile pipe sewer having an internal diameter of 12 inches shall be constructed west along said line to a manhole the west edge of which said manhole shall be 225 feet east of the east line extended of Church Road measured along the center line extended of said sewer where the elevation of said sewer shall be 34.36 feet above datum; from and discharging into a manhole 30 feet northerly from the southerly line extended of Elder Lane and 22 feet easterly from the westerly line extended of Sheridan Road at an elevation of 18.0 feet above datum a brick sewer of cylindrical shape having an internal diameter of 30 inches made with a double ring of sewer brick laid edgewise shall be constructed northerly in Sheridan Road along a line 22 feet easterly from and parallel to the westerly line and said westerly line extended of Sheridan Road to a manhole 23 feet northerly from the southerly line extended of Hawthorne Lane where the elevation of said sewer shall be 20.43 feet above datum; from and discharging into the last mentioned manhole at an elevation of 20.43 feet above datum, a tile pipe sewer having an internal diameter of 27 inches shall be constructed northerly along said line 379 feet to a manhole where the elevation of said sewer shall be 21.34 feet above datum; thence northerly along said line, to a manhole 23 feet north of the south line extended of Willow Street where the elevation of said sewer shall be 22.3 feet above datum; from and discharging into the last mentioned manhole at an elevation of 22.3 feet above datum, a tile pipe sewer having an internal diameter of 12 inches shall be constructed northerly along said line 305 feet to a manhole where the elevation of said sewer shall be 25.0 feet above datum; thence northerly along said line 200 feet to a manhole where the elevation of said sewer shall be 25.4 feet above datum; from the last mentioned manhole a tile pipe sewer having an internal diameter of 18 inches shall be constructed northerly along said line to and discharging into a manhole 23 feet northerly from the southerly line extended of Ash Street where the elevation of said sewer shall be 24.4 feet above datum; from the last mentioned manhole a tile pipe sewer having an internal diameter of 22 inches shall be constructed northerly along said line to and discharging into a manhole 23 feet north of the south line extended of Cherry Street where the elevation of said sewer shall be 23.8 feet above datum; from and discharging into a manhole 22 feet easterly from the westerly line extended of Sheridan Road and 23 feet north of the south line extended of Willow Street at an elevation of 22.5 feet above datum, a tile pipe sewer having an internal diameter of 24 inches shall be constructed west in Willow Street along a line 23 feet north of and parallel to the south line and said south line extended of Willow Street to a manhole 23 feet west of the east line extended of Woodland Avenue, where the elevation of said sewer shall be 23.3 feet above datum; thence west along said line 203 feet to a manhole where the elevation of said sewer shall be 23.91 feet above datum; thence west along said line to a manhole 23 feet west of the east line extended of Fairview Avenue where the elevation of said sewer shall be 24.4 feet above datum; from and discharging into the last mentioned manhole at an elevation of 24.5 feet above datum, a tile pipe sewer having an internal diameter of 22 inches shall be constructed west along said line 206 feet to a manhole where the elevation of said sewer shall be 25.13 feet above datum; thence west along said line to a manhole 23 feet west of the east line extended of Myrtle Street where the elevation of said sewer shall be 25.7 feet above datum; from and discharging into the last mentioned manhole at an elevation of 25.8 feet above datum, a tile pipe sewer having an internal diameter of 15 inches shall be constructed west along said line 220 feet to a manhole where the elevation of said sewer shall be 26.91 feet above datum; thence west along said line to a manhole 23 feet west of the east line extended of Poplar Street where the elevation of said sewer shall be 28.0 feet above datum; from and discharging into the last mentioned manhole at an elevation of 28.1 feet above datum, a tile pipe sewer having an internal diameter of 12 inches shall be constructed west along said line to a manhole the west edge of which said manhole shall be 187 feet west of the west line extended of Poplar Street where the elevation of said sewer shall be 29.2 feet above datum; from and discharging into a manhole 23 feet north of the south line extended of Willow Street and 23 feet west of the east line extended of Fairview Avenue at an elevation of 24.4 feet above datum, a tile pipe sewer having an internal diameter of 12 inches shall be constructed northerly in Fairview Avenue along a line 23 feet westerly from and parallel to the easterly line and said easterly line extended of Fairview Avenue to a manhole the north edge of which said manhole shall be 170 feet north of the north line of Willow Street measured at right angles thereto, where the elevation of said sewer shall be 25.3 feet above datum; from and discharging into a manhole 22 feet easterly from the westerly line extended of Sheridan Road and 23 feet northerly from the southerly line extended of Hawthorne Lane at an elevation of 20.43 feet above datum, a tile pipe sewer having an internal diameter of 27 inches shall be constructed westerly in Hawthorne Lane along a line 23 feet northerly from and parallel to the southerly line and said southerly line extended of Hawthorne Lane to a manhole 23 feet north of the south line extended of Hawthorne Lane from the west where the elevation of said sewer shall be 20.75 feet above datum; thence west along a line 23 feet north of and parallel to the south line and said south line extended of Hawthorne Lane 292 feet to a manhole where the elevation of said sewer shall be 21.39 feet above datum; thence west along said line to a manhole 23 feet west of the east line extended of Woodland Avenue where the elevation of said sewer shall be 22.2 feet above datum; from and discharging into the last mentioned manhole at an elevation of 22.2 feet above datum a tile pipe sewer having an internal diameter of 24 inches shall be constructed west along said line 203 feet to a manhole where the elevation of said sewer shall be 22.77 feet above datum; thence west along said line to a manhole 23 feet west of the east line extended of Fairview Avenue where the elevation of said sewer shall be 23.4 feet above datum; from and discharging into the last mentioned manhole at an elevation of 23.4 feet above datum, a tile pipe sewer having an internal diameter of 18 inches shall be constructed southwesterly in Hawthorne Lane 180 feet to a manhole 23 feet north of the south line of Hawthorne Lane extended from the west where the elevation of said sewer shall be 24.44 feet above datum; thence west along a line 23 feet north of and parallel to the south line and said south line extended of Hawthorne Lane to a manhole 23 feet west of the east line extended of Myrtle Street where the elevation of said sewer shall be 26.0 feet above datum; thence west along said line 220 feet to a manhole where the elevation of said sewer shall be 26.65 feet above datum; thence west along said line to a manhole 23 feet west of the east line extended of Poplar Street where the elevation of said sewer shall be 27.0 feet above datum; from and discharging into the last mentioned manhole at an elevation of 27.0 feet above datum, a tile pipe sewer having an internal diameter of 15 inches shall be constructed west along said line 220 feet to a manhole where the elevation of said sewer shall be 28.35 feet above datum; thence west along said line to a manhole the west edge of which said manhole shall be 23 feet west of the east line extended of Walnut Street where the elevation of said sewer shall be 29.5 feet above datum; from and discharging into a manhole 23 feet north of the south line extended of Hawthorne Lane and 23 feet west of the east line extended of Woodland Avenue at an elevation of 22.8 feet above datum, a tile pipe sewer having an internal diameter of 12 inches shall be constructed north in Woodland Avenue along a line 23 feet west of and parallel to the east line and said east line extended of Woodland Avenue 210 feet to a manhole where the elevation of said sewer shall be 23.8 feet above datum; thence north along said line to a manhole the north edge of which said manhole shall be 377 feet north of the north line extended of Hawthorne Lane where the elevation of said sewer shall be 24.8 feet above datum; from and discharging into a manhole 23 feet north of the south line of Hawthorne Lane extended from the east and 23 feet west of the east line extended of Fairview Avenue at an elevation of 23.4 feet above datum a tile pipe sewer having an internal diameter of 22 inches shall be constructed north in Fairview Avenue along a line 23 feet west of and parallel to the east line and said east line extended of Fairview Avenue to a manhole 23 feet north of the south line extended of Fir street where the elevation of said sewer shall be 24.0 feet above datum; from and discharging into the last mentioned manhole at an elevation of 24.0 feet above datum, a tile pipe sewer having an internal diameter of 15 inches shall be constructed north along said line to a manhole the north edge of which said manhole shall be 25 feet south of the south line extended of the alley in Block 3 of Dale's Addition to the Village of Winnetka where the elevation of said sewer shall be 25.0 feet above datum; from and discharging into a manhole 23 feet west of the east line extended of Fairview Avenue and 23 feet north of the south line extended of Fir Street at an elevation of 24.0 feet above datum a tile pipe sewer having an internal diameter of 20 inches shall be constructed west in Fir Street along a line 23 feet north of and parallel to the south line and said south line extended of Fir Street 207 feet to a manhole where the elevation of said sewer shall be 24.51 feet above datum; thence west along said line to a manhole 23 feet west of the east line extended of Myrtle Street where the elevation of said sewer shall be 25.1 feet above datum; from and discharging into the last mentioned manhole at an elevation of 25.1 feet above datum a tile pipe sewer having an internal diameter of 15 inches shall be constructed west along said line 220 feet to a manhole where the elevation of said sewer shall be 26.47 feet above datum; thence west along said line to a manhole 23 feet west of the east line extended of Poplar Street where the elevation of said sewer shall be 28.0 feet above datum; thence west along said line 220 feet to a manhole where the elevation of said sewer shall be 28.45 feet above datum; thence west along said line to a manhole 23 feet west of the east line extended of Walnut Street where the elevation of said sewer shall be 29.0 feet above datum; from and discharging into the last mentioned manhole at an elevation of 29.0 feet above datum, a tile pipe sewer having an internal diameter of 12 inches shall be constructed west along said line to a manhole the west edge of which said manhole shall be 247 feet west of the west line extended of Walnut Street, where the elevation of said sewer shall be 32.04 feet above datum; from and discharging into a manhole 23 feet north of the south line extended of Elder Lane and 23 feet west of the east line extended of Myrtle Street at an elevation of 25.0 feet above datum, a tile pipe sewer having an internal diameter of 15 inches shall be constructed south in Myrtle Street along a line 23 feet west of and parallel to the east line and said east line extended to Myrtle Street to a manhole 23 feet north of the south line extended of Sunset Road where the elevation of said sewer shall be 26.4 feet above datum; from and discharging into the last mentioned manhole at an elevation of 26.4 feet above datum, a tile pipe sewer having an internal diameter of 12 inches shall be constructed west of Sunset Road along a line 23 feet north of and parallel to the south line and said south line extended of Sunset Road 209 feet to a manhole where the elevation of said sewer shall be 27.5 feet above datum; thence west along said line to a manhole the west edge of which said manhole shall be on the east line extended of Poplar Street where the elevation of said sewer shall be 28.7 feet above datum; from and discharging into a manhole 23 feet west of the east line extended of Myrtle Street and 23 feet north of the south line extended of Sunset Road at an elevation of 26.4 feet above datum a tile pipe sewer having an internal diameter of 12 inches shall be constructed east in Sunset Road along a line 23 feet north of and parallel to the south line and said south line extended of Sunset Road to a manhole the east edge of which said manhole shall be 10 feet west of the west line of Lot 2 of Nicholas Simons and Others' Subdivision where the elevation of said sewer shall be 28.0 feet above datum; from and discharging into a manhole 30 feet north of the south line extended of Elder Lane and 10 feet east of the center line extended of Essex Road at an elevation of 18.6 feet above datum, a brick sewer of cylindrical shape having an internal diameter of 36 inches made with a double ring of sewer brick laid edgewise shall be constructed southerly along a line 10 feet easterly from and parallel to the center line and said center line extended of Essex Road 306 feet to a manhole where the elevation of said sewer shall be 18.93 feet above datum; thence southerly along said line 306 feet to a manhole where the elevation of said sewer shall be 19.25 feet above datum; thence south along said line 306 feet to a manhole where the elevation of said sewer shall be 19.58 feet above datum; thence south along said line 306 feet to a manhole where the elevation of said sewer shall be 19.92 feet above datum; thence south along said line to a manhole 15 feet south of the north line of Winnetka Avenue where the elevation of said sewer shall be 20.25 feet above datum; from and discharging into a manhole 15 feet south of the north line of Winnetka Avenue and 15 feet east of the west line extended of Essex Road from the south at an elevation of 20.3 feet above datum a tile pipe sewer having an internal diameter of 18 inches shall be constructed south in Essex Road along a line 15 feet east of and parallel to the west line and said west line extended of Essex Road 236 feet to a manhole where the elevation of said sewer shall be 20.7 feet above datum; thence south along said line to a manhole 20 feet north of the south line extended of Warwick Avenue where the elevation of said sewer shall be 21.25 feet above datum; from and discharging into the last mentioned manhole at an elevation of 21.35 feet above datum, a tile pipe sewer having an internal diameter of 15 inches shall be constructed west in Warwick Avenue along a line 20 feet north of and parallel to the south line and said south line extended of Warwick Avenue 257 feet to a manhole where the elevation of said sewer shall be 22.21 feet above datum; thence west along said line to a manhole 23 feet west of the east line extended of Abbottsford Road where the elevation of said sewer shall be 23.06 feet above datum; from and discharging into the last mentioned manhole at an elevation of 23.06 feet above datum, a tile pipe sewer having an internal diameter of 12 inches shall be constructed westerly along a line 20 feet northerly from and parallel to the southerly line and said southerly line extended of Warwick Avenue 300 feet to a manhole where the elevation of said sewer shall be 24.56 feet above datum; thence westerly and northerly along said line to a manhole the north edge of which said manhole shall be 210 feet south of the south line extended of Winnetka Avenue, where the elevation of said sewer shall be 25.86 feet above datum; from and discharging into a manhole 30 feet north of the south line extended of Elder Lane and 10 feet east of the center line extended of Woodland Avenue at an elevation of 19.4 feet above datum, a tile pipe sewer having an internal diameter of 27 inches shall be constructed southerly along a line 10 feet easterly from and parallel to the center line and said center line extended of Woodland Avenue 278 feet to a manhole where the elevation of said sewer shall be 19.94 feet above datum; thence southerly along said line 278 feet to a manhole where the elevation of said sewer shall be 20.47 feet above datum; thence south along said line to a manhole 4 feet south of the north line extended to the Public Pathway in Trier Center Neighborhood where the elevation of said sewer shall be 21.0 feet above datum; from and discharging into the last mentioned manhole at an elevation of 21.0 feet above datum a tile pipe sewer having an internal diameter of 12 inches shall be constructed south along said line 302 feet to a manhole where the elevation of said sewer shall be 22.26 feet above datum; thence south along said line to a manhole the south edge of which said manhole shall be 50 feet north of the north line extended of Winnetka Avenue where the elevation of said sewer shall be 23.5 feet above datum; from and discharging into a manhole 4 feet south of the north line extended of the Public Pathway in Trier Center Neighborhood and 10 feet east of the center line of Woodland Avenue at an elevation of 21.0 feet above datum a tile pipe sewer having an internal diameter of 20 inches shall be constructed west along a line 4 feet south of and parallel to the north line and said north line extended of said Public Pathway to and connecting with a manhole to be built at the easterly end of and connecting with the present sewer in Hill Road where the elevation of said sewer shall be and now is 21.5 feet above datum; from and discharging into the present sewer in Hill Road at the west line of Trier Center Neighborhood 23 feet north of the south line of said Hill Road at an elevation of 21.8 feet above datum a tile pipe sewer having an internal diameter of 18 inches shall be constructed west in Hill Road along a line 23 feet north of and parallel to the south line and said south line extended of Hill Road to a manhole 23 feet west of the east line extended of Myrtle Street where the elevation of said sewer shall be 22.5 feet above datum; from and discharging into the last mentioned manhole at an elevation of 22.5 feet above datum a tile pipe sewer having an internal diameter of 15 inches shall be constructed west along said line to a manhole 13 feet westerly from the easterly line extended of Wilson Street measured at right angles thereto where the elevation of said sewer shall be 23.3 feet above datum; from and discharging into the last mentioned manhole at an elevation of 23.3 feet above datum, a tile pipe sewer having an internal diameter of 12 inches shall be laid southerly in Wilson Street along a line 13 feet westerly from and parallel to the easterly line and said easterly line extended of Wilson Street 247 feet to a manhole where the elevation of said sewer shall be 24.49 feet above datum; thence southerly along said line 247 feet to a manhole where the elevation of said sewer shall be 25.79 feet above datum; thence southerly along said line to a manhole the south edge of which said manhole shall be on the north line extended of Winnetka Avenue where the elevation of said sewer shall be 27.0 feet above datum; from and discharging into a manhole 23 feet north of the south line of Hill